

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


33-7-24W
15-045-00587

Company- BURCH DRILLING CO., INC.
Farm-Goff No. 1

SEC. 33 T. 7 R. 24W
S1 SW SW

Total Depth. 3935'
Comm. 10-3-58 Comp. 10-9-58
Suct or Treatm.
Contractor. Burch Drlg. Co.
Issued. 12-13-58

County Graham KANSAS



CASING:

8 5/8" 223' w/160 sx. cem.
4 1/2" 3934' w/125 sx. cem.

Elevation. 2416 KB

Production. 163 BOPD
PWY POT

Figures indicate Bottom of Formations.

SHALE AND shells	1850
shale	2105
anhydrite	2139
shale and lime streaks	2153
lime and shale	3720
lime	3935
Total Depth	

TOPS

Anhydrite	2107
Heebner	3675
Toronto	3699
Lansing	3712

DST #1 3738-3773 Open 1 hr. recovered
180' Gas plus 310' oil cut muddy salt water
plus 380' slightly oil gas cut muddy salt-
water. IBHP 1340#, IFP 0#, FFP 350# FBHP 1280#.

DST #2 3776-3795 Open 1 hr. recovered
385' muddy salt water IBHP 1415#, IFP 45#,
FFP 210#, FBHP 1275#.

DST #3 3828-3870 Open 30 min. recovered
20' oil specked mud. IBHP 230# IFP 0#, FFP 0#
FFP 190#.

DST #4 3870-3900 Open 1 hr. recovered
30' oil plus 20' muddy oil. IBHP 1410#, IFP 0#
FFP 0# FBHP 1285#.