

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-065-01025

Company- BROOKS HALL  
Farm- Huntington No. 1

SEC. 7 T. 7 R. 25W  
SE SE SW

Total Depth. 3870'  
Comm. 2-21-55 Comp. 3-4-55  
Shot or Treated.  
Contractor.  
Issued. 4-23-55

County Graham  
KANSAS



CASING:

8 5/8" 272' w/200 sx cem.  
5 1/2" 3868' w/100 sx cem.

Elevation. 2570 DF

Production. 146 Bbls. oil

Figures Indicate Bottom of Formations.

sand-shale	272	F.F.P.	1050#
shale	1100		
chert-shale	1200	DST #6	3820-55
shale-sand	1660	Tool Open:	1 hr.; weak steady
shale-shells	1855		blow 1 hr.
sand	1945	Rec.:	75' oil spotted mud.
shale-shells	2148	B.H.P.:	920# in 20 min.
Anhydrite	2185		
shale-shells	2685		
lime-shale	3715		
lime	3870		
Total Depth			

TOPS:

Anhydrite	2148
Heebner	3610
Toronto	3641
Lansing	3656
B/Kansas City	3860

DST #1 3647-85 Tool Open  
1 hr., weak blow 1 hr.  
Rec. 65' drilling mud.  
B.H.P. 1070# in 20 min.

DST #2 3687-3715  
Tool Open: 1 hr., strong blow  
1 hr.  
Rec. 1320' gas  
1880' Free oil  
B.H.P. 1160# in 20 min.  
I.F.P. 175#  
F.F.P. 585#

DST #3 3726-60  
Tool Open: 1 hr., strong blow  
1 hr.  
Rec.: 200' Gas  
1140' Free Oil  
300' salt wtr.  
B.H.P. 1110# in 20 min.  
I.F.P. 225#  
F.F.P. 550#

DST #4 3783-3800  
Tool Open: 1 hr., weak blow  
4 min.  
Rec.: 4' VSOCH  
B.H.P. 0# in 12 min.

DST #5 3811-25  
Toop Open: 35 min. strong blow  
throughout test  
Rec.: Gas to surface 28 min.  
3120' free oil  
B.H.P. 1285# in 20 min.  
I.F.P. 400#