

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

15-065-00072

Company THE DERBY OIL COMPANY
Farm Toll No. 1

SEC. 15 T. 7 R. 25W
SW SW SE

Total Depth 4252½

Comm. 11-5-48

Comp. 12-1-48


Shot or Treated.

Contractor. Glenn Peel Drilling Co., Inc.

Issued. 1-1-49

County. Graham

KANSAS



Elevation. 2549.2 ad. /

Production. Dry

CASING:

8 5/8" 147' cem

5 1/2" 4246' cem

Figures Indicate Bottom of Formations.

surface clay, sand	70
sand, shale	108
sand, shale, shells	165
sand	210
clay	260
shale, shells	1015
sand, shale strks	1200
shale, sand strks	1370
shale, shells	1675
shale, shells, red	2125
bod	
shale, shells	2180
anhydrite	2230
shale, shells	2795
lime	2850
shale, lime	3050
shale, shells	3090
lime, shale	3140
shale, lime, iron	3190
strks	
lime, shale, iron	3255
lime, shale	3645
lime	4080
lime, shale	4180
conglomerate	4200
cherty cong.	4215
chert, lime	4230
cherty cong.	4237
lime	4252½
Total depth	

Tops:

Lansing	3739
Base Kansas City	3947
Cherty cong.	4191
reworked Viola	4220
Arbuckle	4237

Rotary T. D. 4250