

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

17-7-25 W


15-005-02354

Company- R.W. SHIELDS & EMPIRE DRLG. CO.
Farm- Barnett No. 1

SEC. 17 T. 7 R. 25W
SW SW NW

Total Depth. ³⁹⁴⁰3490
Comm. 11-22-57 Comp. 12-1-57
Shot or Treated.
Contractor. Empire Drlg. Co.
Issued. 1-11-58

County Graham
KANSAS



CASING:
8 5/8" 272 w/125 sx cem.

Elevation. 2607' KB

Production. Dry

Figures indicate Bottom of Formations.

surface	286
shale-shells	1640
shale-shells-sand	2150
shale-shells	2205
Anhydrite	2240
shale-shells	2810
shale-lime	3130
lime-shale	3305
shale-shells	3430
lime-shale	3700
lime	3940
Rotary Total Depth	

TOPS:
Anhydrite 2205
Heebner 3607
Toronto 3707
Lansing 3722
B/Kansas City 3940

DST #1 3742-60 KB Open 1 hr.
Weak blow for 15 mins. SI 30
mins. Rec. 30 mud. BHP 1100#.

DST #2 3762-84 KB Open 35
mins. Very weak blow for 10
mins. SI 30 mins. Rec 5' mud.
BHP 830#.

DST #3 3860-85 Open 1/2 hr.
Very weak blow for 2 mins.
SI 30 mins. Rec. 12' mud. BHP
1195#.

Ran Wellex Radiation Gaurd Log.