

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02965

Company—CITIES SERVICE OIL CO. et al
Farm—McFadden "B" No. 1

SEC. 28 T. 7 R.25W
NE NW NE
330' & 990' E of N/4c

Total Depth. 3862 PBDT 3846
Comm. 10-22-55 Comp. 11-2-55
Shot or Treated. 1000 gals. acid
Contractor. Glenn W. Peel Drilling Co.
issued. 1-14-56

County Graham
KANSAS



CASING:
8 5/8 @ 238' w/ 225 sx cmt.
5 1/2 @ 3862' w/ 175 sx cmt.
Cmtng. collar @ 2168' w/ 600 sx cmt.

Elevation. 2528

Production 253 BOPD, NW

Figures indicate Bottom of Formations.

clay	150
shale	450
shale & sand	1740
sand	1925
shale	2157
anhydrite	2205
shale & shells	2475
lime & shale	3400
lime	3495
lime & shale	3565
lime	3865
SLM	3862
Total Depth	
Plugged back to	3846
TOPS: (corrected)	
Topeka	3408
Heebner	3603
Dodge	3626
Lansing	3642
Base K. C.	3850

Drld. cmt. to 3846 SLM

Perf. 8/3771-78, no show.
Perf. 46/3758-70
66' oil/3 hrs.
116' oil/5 hrs.
189' oil/8 hrs.