

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


15-179-00176

Company- R.W. SHIELDS & CONTINENTAL OIL CO.
Farm- Heskett No. 1

SEC. 1 T. 7 R. 26W
SE SE SW

Total Depth. 4281'
Comm. 8-16-56 Comp. 8-28-56
Shot or Treated.
Contractor. Empire Drlg. Co.
Issued. 2-9-57

County Sheridan
KANSAS



CASING:
8 5/8" 323' w/175 sx cem.

Elevation. 2560' KB

Production. Dry

Figures indicate Bottom of Formations.

clay-sand	223
sand-shale	343
shale-sand	1950
shale-shells	2165
Anhydrite	2200
shale-shells	2722
lime-shale	3355
shale-shells	3470
lime-shale	3620
lime	3925
shale-lime	4067
shale	4150
shale-lime	4224
Arbuckle	4280 RTD
Arbuckle	4281
Total Depth	

TOPS:

Anhydrite	2165
Heebner	3642
Lansing Kansas City	3680
B/Kansas City	3883
Mississippi	4149
Viola	4176
Arbuckle	4226

DST # 1 - 3698-3715' Open
1 hr. Weak blow for 1 hr.
Rec. 135' myddy salt wtr.
BHP 1150# in 20 min.

DST # 2 -3720-3742 Open $\frac{1}{2}$
hr. Weak blow for 3 min.
Rec. 15' very slightly oil
cut mud. BHP 1115# in 20 min.