


SEP 26 1970

19 7-29W  
SW NW 1E

15-179-20250

Dry / BKC

DRILLERS LOGPOPE NO. 1

<b>CASING RECORD:</b>	<b>OPERATOR:</b>	Hummon Oil, Inc.	<b>DESCRIPTION:</b>
8-5/8" @ 334' w/200 sax cement	<b>CONTRACTOR:</b>	Sage Drilling Co., Inc.	SW NW NE Sec. 19-7S-29W Sheridan Co., Kansas
<b>TOTAL DEPTH:</b>	<b>COMMENCED:</b>	May 12, 1970	<b>ELEVATION:</b> 2899 KB
4250'	<b>COMPLETED:</b>	May 20, 1970	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil & Clay	0	42	Log Top
Clay & Sand	42	192	
Sand	192	252	anhydrite 2554
Shale	252	490	2593
and	490	550	B. "
shale	550	1560	Heelover 3946
Sand	1560	1665	Taronto 3972
Shale	1665	1775	LKC 3987
Sand	1775	1840	LKC 1703n 4155
Shale	1840	2193	
Red Bed	2193	2264	
Sand	2264	2357	
Shale	2357	2555	
Anhydrite	2555	2614	
Shale & Shells	2614	2880	
Lime & Shale	2880	3885	
Lime	3885	4055	
Lime & Shale	4055	4250	4 1/2" @ 4249/150 sax

Pope No. 1

19-7-29W