

303 East Murdock
Wichita, Kansas

JUL 19 1969

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company Dreiling & Hiko Bell Mining & Oil Company
Route 2
Victoria, Kansas 67671

Farm Gilchrist No. 1

Total Depth 4280'

Comm. 3-31-69 Comp. 4-8-69

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas 67671

15-179-20197
Sec. 21 Twp. 7 Rng. 30 W

Location SW SW NW

County Sheridan

Elevation: 2942' K. B.

2939' D. F.

2937' G. R.

Casing Record
348' - 8 5/8"
4279' - 4 1/2"

Cement Record
200 sacks cement
175 sacks 50/50 pozmix

Production:
oil

Figures Indicate Bottom of Formations

0'	75'	Top Soil & Sand
75'	165'	Surface Clay & Sand
165'	305'	Sand & Gravel
305'	348'	Blue Shale
348'	2218'	Shale
2218'	2225'	Hard Sand
2225'	2599'	Shale & Sand
2599'	2638'	Anhy.
2638'	3330'	Shale & Lime
3330'	3456'	Shale
3456'	3966'	Shale & Lime
3966'	4280'	Lime
4280'	T.D.	

STATE OF KANSAS)
) ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Gilchrist #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 11th day of April 1969.



Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

commission expires: September 19, 1970.