

COMPANY: Gulf Energy & Minerals Company - U.S. SEC. 24 T. 7S R. 31W  
WELL NAME: McCormick #4-24 LOC. 1980' FNL & 660' FWL  
RIG NO. #4 COUNTY: Thomas

TOTAL DEPTH 4335' ELEVATION

COMMENCED: 1-18-77 COMPLETED: 1-26-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 471' w/175 sx. 50/50 poz., 2% gel, 3% cc. and 100 sx.  
common, 3% cc.

PRODUCTION: 5 1/2" @ 4334' w/350 sx. 50/50 poz., 2% gel, 10% salt, 3/4 of  
1% CFR2

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	450
Shale	481
Shale & Shells	1330
Shale & Sand & Shale	1955
Sand & Shale	2160
Shale	2310
Sand	2410
Shale & Sand & Redbed	2606
Redbed & Shale	2990
Shale & Lime	3205
Redbed & Shale	3458
Redbed & Shale & Lime	3595
Redbed & Shale	3650
Redbed & Shale & Lime	3805
Shale & Lime	3965
Lime	4335
<u>ROTARY TOTAL DEPTH</u>	<u>4335</u>