

SIDE ONE

AFFIDAVIT OF COMPLETION FORM

26-7-31W. (REV) ACO-NUL

2nd

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR John R. Evans

API NO. 15-193-20230

ADDRESS 405 Fourth

COUNTY Thomas

Claflin, Kansas 67525

FIELD _____

**CONTACT PERSON _____

PROD. FORMATION K.C.

PHONE _____

LEASE RALL

PURCHASER _____

WELL NO. 1

ADDRESS _____

WELL LOCATION SE SE SE

DRILLING Thunderbird Drilling, Inc.

CONTRACTOR _____

ADDRESS P.O. Box 18407

330 Ft. from South Line and

330 Ft. from EAST Line of

the SE SEC. 26 TWP. 7S RGE. 31W


Wichita, Kansas 67218

PLUGGING _____

CONTRACTOR _____

ADDRESS _____

WELL PLAT



KCC _____
KGS _____
(Office Use)

TOTAL DEPTH 4370

PBTD _____

SPUD DATE 1/25/82 DATE COMPLETED 2/3/82

ELEV: GR 2982 DF 2984 KB 2987

DRILLED WITH (~~CABLE~~) (ROTARY) (~~XXX~~) TOOLS

Amount of surface pipe set and cemented 412' w/300 sx. DV Tool Used? no

AFFIDAVIT

STATE OF KANSAS, COUNTY OF BARTON SS, I, _____

John Roy Evans OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS _____ (FOR)(OF) _____

OPERATOR OF THE RALL LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE _____ DAY OF _____, 19____, AND THAT

SIDE TWO

WELL LOG

26-7-31w

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Filed by Thunderbird Only			Anhydrite	2650
			Top KA	3829
			Heebner	4022
			LANSING	4062
			Base KC	4306
			MARMATON	4342
			RTD	4371

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used				Depth interval treated	
250 gal mod Acid 15%				4239-42	
750 gal mod Acid 15%				4239-42	
6000 gal gel Acid 15%				4239-42	
Date of first production 4-10-82		Producing method (flowing, pumping, gas lift, etc.) Pumping		Gravity 36.5	
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	3 bbls.		50% MCF	3 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Perforations 4239-42		

D.S.T #1 - 4170-4255 (MISRUN)							
----------------------------------	--	--	--	--	--	--	--

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	412	60-40	300	
Production	7 7/8	4 1/2	9.5	4367	60-40	150	300# SEIT 387# CACH

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----------	-------------	--------------

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
4	J-T	4239-42

TUBING RECORD

Size	Setting depth	Pecker set at
2 3/8	4325	

DRILLERS LOG

26-7-31W

Company Thunderbird Drilling, Inc.

Contractor Thunderbird Drilling,

Elevation

JUL

Farm Rall

Well No. 1

Casing 8 5/8" @ 412' w/300 sx

Location SE SE SE, Sec. 26-7S-31W

County Thomas County, Ks.

Production 4 1/2" @

<u>From</u>	<u>To</u>	<u>Description</u>
0	412	Surface hole
412	1436	Shale & Sand
1436	2396	Shale
2396	2452	Sand
2452	2545	Shale & Sand
2545	2649	Shale
2649	2692	Anhydrite
2696	2755	Shale & Lime
2755	3020	Lime & Shale
3020	3252	Shale & Lime
3252	3380	Shale & Sand
3380	3425	Shale
3425	4370	Lime
4370	R.T.D.	

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

I, Burke Krueger, of Thunderbird Drilling, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Rall #1.

BK

Subscribed and sworn to before me this 4th day of March, 19 82

Gloria DeJesus
Gloria DeJesus Notary Public

My commission expires: 3-25-84