

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 181 — 20,207
County Number

Operator

Rincon Operating Co.

Address

5180 Lincoln Street, Suite 700 Denver, Colo 80203

Well No.

#1

Lease Name

Sramek

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Stoeppelwerth Drilling

Geologist

RTD

Spud Date

6/5/81

Date Completed

8/4/81

Total Depth

5030 P.B.T.D.
5020' 5045' LTD

Directional Deviation


Oil and/or Gas Purchaser

Asamera Oil (U.S.) Inc.

S. 14 T. 7 R. 37 K W

SW NE

County Sherman

640 Acres
N

Locate well correctly

Elev.: Gr. 3428

DF KB 3432

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	563'	Common	400	3% CaCl
Production	7 7/8"	5 1/2"	15.5#	5042'	50/50 poz	200	3/4% CFR-2 2% gel, 10% Salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF	Jet	4966-69'; 4842-45'; 4832-36'; 4817-27'; 4817-4806
TUBING RECORD					
Size	Setting depth	Packer set at			
2 7/8"	4925'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized with 750 gal MCA	4966-69'
Acidized with 1500 gal MCA	4842-45'; 4832-36';

INITIAL PRODUCTION

Date of first production 7/30/81		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 30 bbls.	Gas 0 MCF	Water 30 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold) NA			Producing interval(s) 4817-4926' 4806-4845'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rincon Operating Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:									
Well No. 1	Lease Name Sramek		Oil								
S 14 T 7S R 37W E W											
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.									
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.											
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="padding: 5px;">NAME</th> <th style="padding: 5px;">DEPTH</th> </tr> </thead> <tbody> <tr> <td style="padding: 5px;">Lansing</td> <td style="padding: 5px;">4250</td> </tr> <tr> <td style="padding: 5px;">Marmaton</td> <td style="padding: 5px;">4610</td> </tr> <tr> <td style="padding: 5px;">Cherokee</td> <td style="padding: 5px;">4800</td> </tr> </tbody> </table>	NAME	DEPTH	Lansing	4250	Marmaton	4610	Cherokee	4800
NAME	DEPTH										
Lansing	4250										
Marmaton	4610										
Cherokee	4800										
DST #1 4256-4300' Open 15 min, SI 30 min Open 60 min, SI 90 min Rec'd 410' MW w/oil specks IHP 2258#, FHP 2239#; ISIP 1276# FSIP 1306#, IFP 111-121#, FFP 193-243#											
DST #2 4330-4350 Misrun - packer failed											
DST #3 4310-4350' Open 15 min, SI 30 min Open 60 min, SI 90 min Rec'd 600' MW IHP 2239#, FHP 2199#, ISIP 1326#, FSIP 1326#, IFP 121-132#, FFP 223-304#											
DST #4 4615-4645' Open 15 min, SI 30 min Open 30 min, SI 30 min Rec'd 30' Mud w/oil flecks IHP 2408#, FHP 2368#, ISIP 1117#, FSIP 968#, IFP 81-60#, FFP 101-71#											
DST #5 4805-4830' Open 15 min, SI 30 min Open 60 min, SI 90 min Rec'd 240' Gas & 480' fl w/ 420' GCMO 7 60' W		IHP 2566#, FHP 2536#, ISIP (no reading) FSIP 1087#, IFP 111-132#, FFP 182-233#									
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.											
Date Received	 C. A. HANSEN DRLG & PROD MGR 9/30/81										
	Signature Title Date										