

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- MIAMI PETROLEUM COMPANY, INC.
Farm- W. W. Bear "C" No. 1

SEC. 18 T. 7 R. 37W
C SW SW

15-181-00007

Total Depth. 5500'
Comm. 8-25-58 Comp. 9-12-58
Shot or Treated.
Contractor.
Issued. 12-6-58

County Sherman
KANSAS



Elevation. 3498 RB

Production. Dry

CASING:

9 5/8" 354.98' w/250 sx. cem.

Figures Indicate Bottom of Formations.

shale w/sand streaks	184
shale w/sand streaks	394
shale & calcareous shale	1454
sand & calcareous shale	1575
calcareous shale w/sand streaks	1860
shale w/sand & lime streaks	2557
red shale	2584
red shale w/anhydrite, lime and sand streaks	2990
red shale w/anhydrite streaks	3100
salt and anhydrite	3150
anhydrite	3182
red shale w/anhydrite, sand & dolomite streaks	3693
lime	3699
red shale w/lime, sand & anhydrite streaks	3780
red shale w/lime streaks	3840
lime and gray shale streaks	3904
shale w/lime streaks	3946
lime & shale streaks	4039
lime & shale streaks	4328
shale	4334
shale and lime streaks	4350
shale and lime streaks	4413
chalky lime & shale streaks	4600
chalky lime w/shale streaks	4650
chalky lime w/shale streaks	4780
chalky lime w/shale streaks	4861
chalky cherty lime w/shale streaks	4970
varicolored shale w/lime & conglomerate streaks	5034
varicolored shale w/lime and conglomerate streaks	5084
shaley conglomerate	5098
lime and chert	5121
lime w/dolomite & chert streaks	5167
dolomite	5172
dolomite w/lime and chert streaks	5290
lime with chert	5349
chalky lime w/chert streaks	5446
dolomite	5492
Dolomite	5500
Total Depth	

Ran Schlumberger from 5499-358'

TOPS	
Anhydrite	3150
Heebner	4328
Lansing Kansas City	4413
Marmaton	4717
Cherokee	4852
Mississippian	5098
Arbuckle	5446