

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey
KANSAS
WICHITA BRANCH

API No. 15 — 181 — 20,056
County Number

Operator

Benson Mineral Group, Inc.

Address

2200 Anaconda Tower, Denver, Colo. 80202

Well No.

2-34

Lease Name

Peters

Footage Location

2310 feet from (N) ~~XX~~ line 330 feet from (E) (W) line

Principal Contractor

B & N Drilling

Geologist

Spud Date

7/24/79

Date Completed

7/25/79

Total Depth

1030'

P.B.T.D.


Directional Deviation

Oil and/or Gas Purchaser

Loc. SW SW NW

County Sherman

640 Acres



Locate well correctly

Elev.: Gr.

3540

DF

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	7 7/8	5 1/2		350'		65	
PRODUCTION	4 3/4	2 7/8"		1017'		22	10 bbls gelled water

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
None		

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
1 SPF		909-51

TUBING RECORD

Size	Setting depth	Packer set at
None		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Foam frax x 40,000# 20-40 sand x 22,000 gal 70 quality foam containing 52 gal Pen-5 surfactant, 2% KCl x 2#/gal 20-40 sand as follows: run 2,000 gal foam pad followed by 20,000 gal foam x 2#/gal 20-40 sand.	909-51

INITIAL PRODUCTION

Date of first production
SIGW 10-5-79

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

Gas

Water

Gas-oil ratio

bbls.

MCF

bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Benson Mineral Group, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 2-34	Lease Name Peters	
S <u>34</u> T <u>7S</u> R <u>38W</u> ^E _W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
soil	0	8		
shale	8	40		
sand	40	320		
shale	320	604		
sand/shale	604	1023		
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	<u>Paul C. Ellison (ps)</u> Signature <u>Paul C. Ellison, Vice President</u> Title <u>September 18, 1981</u> Date
---------------	--