


WELL LOG (BUREAU) - KANSAS GEOLOGICAL SURVEY  
 412 Union National Bldg., Wichita, Kansas

Company - SINCLAIR PRAIRIE OIL CO.  
 Farm - Millie Hempler No. 1

SEC. 27 T. 8 R. 16 W  
 CS/2 SW SW

15-163-03695

County. Rocks  
 KANSAS



Total Depth. 3121'  
 Comm. 3-27-45 Comp. 4-16-45  
 Shot or Treated. 6000 gals acid.  
 Contractor. Harbar Drlg. Co.  
 Issued. 6-16-45

CASING:

10 3/4" 1250' Cem.  
 5 1/2" 3119' Cem.

Elevation. \_\_\_\_\_

Production. Pot. 84 BPD

Figures Indicate Bottom of Formations.

surface clay & sand	40
shale & shells	650
pyrite strks	660
shale & shells	670
shale sdy	940
sand & shale	1000
shale & shells	1010
red rock-shells	1239
lime-anhydrite	1247
anhydrite	1270
shale & shells	1420
sand-shale-lime	1515
shale & shells	1710
lime	1815
shale & lime	1890
lime & brkn shale	1919
chert-rough	1920
lime	1980
shale	2074
lime	2121
shale & lime	2125
lime	2175
lime brkn	2190
lime & shale	2250
lime	2280
lime & shale	2307
lime	2365
lime brkn	2400
lime	2434
shale & lime	2605
shale	2810
lime & shale	2849
lime	2925
shale	2942
lime	3121
Total Depth	

Top of Lansing-KC 3075'

Sli sh of oil 3075-77'  
 Good oil stain, strong odor &  
 lgt por. 3119-21'