


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - DERBY OIL COMPANY  
Farm - Harrison No. 1

SEC. 28 T. 8 N. 16 W  
CS/2 SE NE

15-163-00263

County. Rocks  
KANSAS.



Total Depth. 3445'  
Comm. 5-31-45 Comp. 6-17-45  
Shot or Treated.  
Contractor. Glenn Peel  
Issued. 7-21-45

CASING:

10 3/4" 280' Cem.  
5 1/2" 3225' Cem.

Elevation \_\_\_\_\_

Production. Pot. 60 B.

Figures Indicate Bottom of Formations.

clay & shale & shells	0-130
clay & shale	280
shale & shells	739
shale	855
sand	895
shale & shells	960
shale & red bed	1200
anhydrite	1254
shale & red bed	1352
shale & shells	1550
shale & salt	1655
shale & shells	1723
lime & shale	1804
shale & shells	1850
lime	1956
lime & shale	2825
lime	3221
shale & lime	3230
lime	3445
Total Depth	

Topo: (Geological Survey)

Topeka	2803
Lansing	3058
Rev. Arbuckle	3416
Arbuckle	3428

Fair stain 2824-30'; s.s.o. 2903-09'  
good odor & sat. 2988-96'; lgt stain  
3098-98'; good odor & fair stain 3100-  
04'; good odor & sat. 3165-68'; Perf.  
12/3168-70' s.s.o. 3164 Perf. 12/3162-  
66' fillup 400' salt wtr. 14 hrs.;  
Perf. 36/3094-3105' 500A 125' oil in  
hole 12 hrs. 5000 & plus 1000 butane  
shut down 12 hrs. 1525' fluid. Swab  
down & swab 2 1/2 BOH for 12 hrs.  
plus 3% wtr. - Comp. for 60 BO