

**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas


Company- DAVIS BROS-TRANSIT CORP.  
 Farm- Zimmerman "A" No. 1

SEC. 32 T. 8 R. 16W  
 C SW NE

15-103-00905

Total Depth. 3472'  
 Comm. 12-16-58 Comp. 12-26-58  
 Shot or Treated.  
 Contractor.  
 Issued. 3-7-59

County Rooks KANSAS



Elevation. 1966' RB

Production. Dry

CASING:  
 8 5/8" 176' cem w/130 sx.

Figures Indicate Bottom of Formations.

surface, clay & sand	120
shale & shells	445
sand	700
shale & shells	1100
shale & red bed	1242
Anhydrite	1281
shale, shells & red bed	1390
shale	1920
shale & lime	2040
lime & shale streaks	2155
lime	2270
shale & lime	2300
shale & lime streaks	2405
lime & shale	2440
shale & lime	2830
lime & shale	3189
lime	3362
lime & shale	3430
Conglomerate	3447
Arbuckle	3472
Total Depth	

TOPS:	
Topeka	2842
Heebner	3066
Toronto	3086
Lansing	3106
Base Kansas City	3359
Conglomerate	3434
Arbuckle	3447