

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- Cities Service Petroleum Co.
 Farm- Adams "A" No. 5

SEC. 33 T. 8 R. 16W
 C NE SE

15-163-0097

Total Depth. 3358' PBTB 3339'
 Comm. 12-14-62 Comp. 12-28-62
 Shot or Treated.
 Contractor. Peel Brothers, Inc
 Issued. 4-6-63

County Rocks KANSAS



Elevation. 1950 DF

CASING:
 8 5/8" 239' cem w/200 sx.
 5 1/2" 3357' cem w/175 sx.
 DV tool 1260' cem w/400 sx. - 200 cu. ft. Stratacrete
 Figures indicate Bottom of Formations. Production. 27 BOPD - 150 BWPD

soil & shale	20
lime	40
sand, shale & shells	239
shale & shells	480
shale & sand	550
shale & shells	815
shale & sand	835
sand & shale	860
sand	935
shale and red bed	1239
Anhydrite	1268
shale & shells	1630
shale & lime	1810
lime & shale	2020
shale & lime	2195
lime & shale	2755
shale & lime	2815
lime	3360 RTD

3360 Rotary TD - 3358 SIM from cable
 tool floor (1' above ground level).
 Total Depth

Plugged back to 3339'

TOPS: LOG

Anhydrite	1239
Topeka	2794
Heebner	3015
Toronto	3039
Lansing	3057
Base Kansas City	3315