


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Adams "B" No. 1.

15-163-01331
SEC. 33 T. 8 R. 16 W
C S $\frac{1}{2}$ SE NE
3 30' N 660' W E $\frac{1}{4}$ Cor.

Total Depth. 3126' PB 3120'
Comm. 7-6-44 Comp. 8-8-44
Shot or Treated.
Contractor. Holm Drlg. Co.
Issued. 10-28-44

County. Rocks
KANSAS



CASING:
8 5/8" 248' Cem.
4 1/2" 3107' Cem.

Elevation. _____

Production. Phy. Pot. 192 B.
22 BW

Figures Indicate Bottom of Formations.

shale & shells	0-248
shale & lime shells	410
shale sdy & shells	630
sand & iron shells	740 ✓
shale & shells	780
sand & iron	890 ✓
shale red	1153
shale & shells	1228
anhydrite	1263
shale & shells	1650
shale & salt shells	1680
lime & shale brks	1795
lime brkn	1915
shale & shells	1950
lime & shale	2020
lime & shale brks	2550
shale & shells	2600
lime & shale brks	2979
lime	3115
3115 Rot. TD = 3114 SLM	
lime	3126
Total Depth	

Corr. Top Lansing 3066
Penetration 60
TD 3126
PB w/cement 3126 to 3120
PB Pen. 54

Fillup:
200' oil in 16 hrs. @ 3122
725' fluid (250' wtr) in
16 hrs. @ 3126

Acid:
8-19-44 500 Gals.
8-21-44 3000 Gals.