

**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas


Company- Murfin Drilling Co. - R.A. Comeau  
 Farm- Adams "B" No. 1

SEC. 33 T. 8 R. 16W  
 C SE SW

15-103-51332

Total Depth. 3375'  
 Comm. 8-21-61 Comp. 8-28-61  
 Shot or Treated. No  
 Contractor. Murfin Drilling Company  
 Issued. 4-6-63

County Rooks KANSAS



Elevation. 2004' KB

Production. 25 BOPD

**CASING:**

8 5/8" 183' cem w/150 sx.  
 5 1/2" 3375' cem w/100 sx.

Figures Indicate Bottom of Formations.

|                       |          |
|-----------------------|----------|
| shale                 | 220      |
| shale-shells          | 475      |
| sand & shale          | 585      |
| shale                 | 764      |
| iron pyrite-hard sand | 788 ✓    |
| sand                  | 950      |
| red bed-shale         | 975      |
| red bed               | 1253     |
| Anhydrite             | 1288     |
| shale shells          | 1625     |
| salt-shale            | 1745     |
| shale-lime shells     | 1925     |
| shale-lime            | 2125     |
| lime                  | 2345     |
| lime-shale            | 2619     |
| shale-lime            | 2920     |
| lime                  | 3375 RTD |
| Total Depth           |          |

**TOPS:**

|                            |      |
|----------------------------|------|
| Anhydrite                  | 1253 |
| Base/ <del>Anhydrite</del> | 1288 |
| Topeka                     | 2855 |
| Heebner                    | 3075 |
| Toronto                    | 3094 |
| Lansing/Kansas City        | 3115 |
| Base/ Kansas City          | 3345 |