

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **ROSENCRANTZ-DEMIS ENTERPRISES, INC.**
 Farm- **Gager** No. **1**

SEC. **28** T. **8** R. **16W**
C NE SE

15-103-02637

Total Depth. **3275'**
 Comm. **11-12-62** Comp. **12-30-62**
 Shot or Treated.
 Contractor. **Co. Tools**
 Issued. **6-12-65**

County **Rooks**
KANSAS



CASING:

8" 121'
4 1/2" 3309'

Elevation. **1938' DF**

Production. **DRY**

Figures Indicate Bottom of Formations.

ALL MEAS FR R.B.

Gray granular to fossiliferous LM., intercrystalline porosity, slight odor, some free oil in wet samples and staining. <u>Test before Abd.</u>	2962-66	Topeka Heebner Toronto Lansing-Kansas City	2794 drillers. 3015 Samples 3033 " 3056 "
Gry. crystalline to fossiliferous LM. pinpoint porosity, faint odor, free oil and partical staining. <u>Test.</u>	3033-38		

White fossiliferous LM. poor por- osity, show free oil and partical staining, no odor. <u>Doubtful impor- tance.</u>	3081-84
--	---------

White fossiliferous LM., intercrystal- line porosity, fair odor, some free oil and staining. <u>Test.</u>	3094-3100
---	-----------

White to gray fossiliferous to oola- castic LM., fair intercrystalline porosity, fair odor, staining and free oil in wet samples. <u>Test.</u>	3113-18
---	---------

Same lithology as above with lesser shows of oil and porosity. <u>Doubt- ful importance.</u>	3123-28
---	---------

White oolacastic LM., no odor, staining with show of free oil in wet sample. <u>Test if looks favorable on electric log.</u>	3150-56
--	---------

White oolacastic LM., faint odor, stained with some free oil in wet samples. <u>Test.</u>	3161-65
---	---------

Gray oolacastic to oolitic LM., intercrystalline to vugular porosity, fair odor, abundant free oil in wet samples and saturated staining. <u>Test.</u>	3218-27
---	---------

Light gray fossiliferous to crystalline LM., no odor, show free oil and staining. <u>Test.</u>	3236-40
--	---------

White crystalline to chalky LM., no odor, poor crystalline porosity, show free oil and partical staining. <u>Test if looks favorable on electric log.</u>	3245-53
---	---------

White to light gray fossiliferous to crystalline LM., faint odor, partical staining and some free oil in wet samples. <u>Test.</u>	3270-75
---	---------

Total Depth	3275
-------------	------

TOPS:
 Anhydrite **1260 Driller**