

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-163-01333

Company - CITIES SERVICE OIL CO.
Farm - Adams "C" No. 1

SEC. ³³ T. 8 R. 16W
SE 1/4 SE

990' S and 990' E of NW cor.
County. Rooks

Total Depth. 3295' P.B. 3165

Comm. 6-15-47 Comp. 6-26-47

Shot or Treated. 1000 Gals. 3068-73, 2000 gals 3095-3116, 2000 gals 3128-52,

Contractor. Holm Drilling Co. 7-30-47

Issued. 10-18-47

KANSAS



Elevation. 1951

Production. Swab 32 oil, 18 wtr.

Figures Indicate Bottom of Formations. 24 hrs. 98-3-47)

clay & shells	40
shale & shells	435
sand " shells	455
shale & shells	510
sand & shale	765
shale & lime	830
sandy shale	870
sand	940
red shale & shells	1228
anhydrite	1258
shale " shells	1675
salt, shale & shells	1725
lime shale	1880
shale	1915
lime shale	2280
lime	2310
lime " shale	2550
shale & shells	2605
lime " shale	2745
shale " shells	2835
lime	2900
lime & shale	2945
lime	2970
lime & shale	2999
lime	3104
lime & shale	3120
lime broken	3131
lime soft	3136
lime broken	3147
lime	3250
lime broken	3275
shale	3290
lime	3295
Total Depth	3295

TOPS:

Corr. Lansing	3068'
Penetration	227'
Total Depth	3295'

Drilled Cement to 3278 $\frac{1}{2}$ S.L.M.

Perf. 31 shots 3144-52
Perf. 24 shots 3128-33
Perf. 38 shots 3106-16
Perf. 15 shots 3095-3101
Perf. 8 shots 3068-73

16 gallons water & 2 gals. oil per hr.

7-7/8" Rotary Hole.