

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


Company - CITIES SERVICE OIL CO.  
Farm - Adams "C" No. 2

SEC. 33 T. 8 R. 16W  
SE SW SE  
330' N & 990' E of S/4 Corner

Total Depth. 3310'  
Comm. 12-12-48 Comp. 12-19-48  
Shot or Treated. Acid. 4/5000 gals. 12-31-48  
Contractor. R. W. Rine Drlg. Co.  
Issued. 2-12-49

County. Rooks

KANSAS



Elevation. 1966 Ind.

Production. Pmp. 80 oil, 122 wtr,  
24 hours.

Figures Indicate Bottom of Formations.

CASING:  
8-5/8" 250' Cem. 4/150 Sx.  
4-1/2" 3307' Cem. 4/150 Sx.

surface soil, shale	
& shells	250
shale & shells	1245
anhydrite	1285
sand & shale	1745
shale & lime	2320
shale	2470
shale & lime	3070
lime	3310
3310 RTD = 3307 S.L.M.	
Total Depth	

Tops, Corr.:	
Lansing	3070
Penetration	237
Perf. Pen. Lansing	202

Drilled cement to 3297' SLM

Perf. 21 shots 3263-72  
Perf. 16 shots 3256-62  
Perf. 6 shots 3242-50  
25 gals. oil in 19 hrs.  
Perf. 24 snots 3242-50  
Perf. 32 shots 3140-48  
Perf. 17 shots 3129-34  
Perf. 24 shots 3196-3202  
Perf. 24 shots 3110-18  
Perf. 18 shots 3072-77  
Perf. 17 shots 3052-56

12-31-48 Acid. 1500 gals. 3242-72  
12-31-48 Acid. 500 gals. 3196-3202  
12-31-48 Acid. 2000 gals. 3110-48  
12-31-48 Acid. 1000 gals. 3052-77