

15-163-60421


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Dancer No. 1

SEC. 4 T. 8 R. 17W
NE NE NW

Total Depth. 3387 P.B. 3180
Comm. 2-9-52 Comp. 2-19-52
Shot or Treated. 1000 gal. acid
Contractor. Murfin Drlg.
Issued. 4-12-52

County Rocks
KANSAS



CASING:

8" 128'
5" 3353'

Elevation. 1881 D.F.

Production. 1883 Swb. 26 1/2 bbls.
. no wtr.

Figures Indicate Bottom of Formations.

shale, shells	128
shale	550
sand	580
shale	735
sand	1000
sand, shale	1050
red bed	1273
anhyd.	1304
shale	1550
shale, lime	1675
li e	1570
lime brkn	1900
shale, lime	2065
lime	2155
shale, lime	2630
shale	2764
lime	3270
lime, shale	3355
lime, shale	3387
Total Depth P.B. 3180	

Tops: Scout	
Topeka	2799
Heebner	3011
Mansing	3055
Arbuckle	3349

D.S.T. # 1 3057-3108 1 hr. 8' mud, 300 BHP
D.S.T. # 2 3143-58 30 min. 60' slightly
oil cut mud, 270' heavily oil cut mud,
30' wtr. 1150 BHP

Cable Tool information - Drilled to 3337.
Slight trace oil @ 10 bbls. wtr. per day.
P.B. to 3180. Perf. 3148-51. No fluid. Perf.
3148-52 and shut down 14 hrs. had 300'
wtr. & 1/2 blr. oil. Az. 1000 gal. Hole filled
2300' oil in 14 hrs. No wtr.