


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BAY PETROLEUM & VIRGINIA DRILG..
 Farm- Hunter No. 2

SEC. 4 T. 8 R.17W
 SW SE SW

Total Depth. 3459
 Comm. 9-19-52 Comp. 10-2-52
 Shot or Treated.
 Contractor. Virginia Drlg.
 Issued. 10-25-52

County Rocks
 KANSAS



CASING:
 8 5/8" 212'

Elevation. 1938 D.F.

Production. Dry

Figures Indicate Bottom of Formations.

surface rock	30
shale	40
shale, shells	150
sand	170
shale, shells	192
shale blue	525
shale	550
sand	730
shale, shells	800
sand, shale	1300
anhyd.	1385
shale	1415
shale, shells	1790
lime, shale	1825
lime	1910
lime brkn	2025
lime, shale	2135
lime	2200
lime, shale	2435
shale, shells	2650
shale	2824
shale, lime	3032
lime	3052
lime, shale	3118
lime	3220
shale, lime	3293
lime	3346
shale, lime	3409
Congl.	3459
Total Depth	

Tops:

Topeka	2867
Heebner	3070
Lansing-K.C.	3112
shy. Congl.	3374
chty. Congl.	3417

D.S.T. 3013-43 op. 1 hr.
 Rec. 240' S W BHP 1230#.
 DST 3281-3344 op. 1 hrs. Rec.
 135' SW 15" BHP 1110 acid
 D.S.T. 3346-3388 op 1/2 hr. R c,
 65' muddy wtr. 790# BHP
 Shy congl. 3374
 chty Cong. 3417