


15-163-03271

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company— VIRGINIA DRILLING CO., INC &
BAY PETROLEUM CORPORATION
Farm— Hunter No. 3

SEC. 4 T. 8 R.17W
NW SW SW

Total Depth. 3417
Comm. 4-17-53 Comp 4-29-53
Shot or Tested.
Contractor Virginia Drilling Co.
Issued. 7-18-53

County Rooks
KANSAS


CASING:

8 5/8 set at 197'
5 1/2 set at 3403'

Elevation. 1953 DF

Production. 107 BOPD, 2% water

Figures in parentheses Bottom of Formations.

surface rock	70
shale	160
sand & shale	197
shale	275
shale & shells	820
sand & shale streaks	950
shale	1270
anhydrite	1298
red rock	1315
shale & shells	1740
lime & shale	2340
shale & shells	2455
shale & lime streaks	2545
lime & shale	2795
shale & broken lime	2865
lime	3417
Total Depth	

TOPS:	
Topeka	2869
Toronto	3090
Lansing KC	3110
Conglomerate	3395
Arbuckle	3402

DST #1: 3149-88, open 1 hr. rec. 15'
mud BHP 0#

DST #2: 3190-3216, open 1 hr. rec.
1200' fluid, 300' HO&GC thin mud,
660' O&GCW, 240' SW, BHP 1100#

DST #3: 3261-3303, open 1/2 hr. rec.
10' SOCM, BHP 0#

DPDD 11' test 10 60)PH--500 Acid.
Swab 7 BOPH