

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. G. HANSEN
Farm- Russ

No. 1

SEC. 29 T. 8 R. 17W
NW NW NW

15-163-03200

Total Depth. 3351'

Comm. 2-4-58

Comp. 2-14-58


County Rooks

KANSAS

Shot or Treated.

Contractor. C-G Drlg.

Issued. 5-31-58



CASING:

8 5/8" 178.56'

5 1/2" 3333'

Elevation. 1902' RB

Production. 25 BOPD

All Meas. from top of RB.

Figures Indicate Bottom of Formations.

sand-shale	810
sand	960
red bed	1252
Anhydrite	1290
shale-shell	1730
lime-shale	2808
lime	2952
lime-shale	3015
lime	3337
Arbuckle	3344 RTD
lime	3351 CTTD
Total Depth	

TOPS:

Anhydrite (scout)	1253
Topeka	2810
Heebner	3024
Toronto	3045
Lansing-Kansas City	3064
Base Kansas City	3291
Basal Penn. lime	3310
Arbuckle	3331

DST #1 3054-3080, open 30 min, and rec.
9' drilling mud, no pressures.

DST #2 3127-52, open ½ hr, rec. 6' VSOCM.
No pressures.

DST #3 3153-65, open 1½ hrs, rec. 60' G
above 225' fluid, 100' was GOCM,
60' GHOCM, 30' MGO, 15' O, 20' SW.
IBHP 1055#, FBHP 715#, FFP 85#.

DST #4 3208-30, open 1 hr, rec. 35' SOCM
IBHP 945#, FBHP 90#, FFP 20#.

DST #5 3239-70, open 1 hr, rec. 13' M,
IBHP 1143#, FBHP 65#, FFP 30#.

DST #6 3333-44, open 1 hr, rec. 22' SOCM
BHP 173#.