

15-163-00078

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- MURFIN DRILLING CO. ET AL
Farm- Turner "B" No. 1

SEC. 8 T.8 R.17
NE NW NE

Total Depth. 3363
Comm. 2-6-54 Comp. 2-16-54
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 5-1-54

County Rocks

KANSAS



Elevation. 1886 R.B.

Production. Dry

Figures indicate Bottom of Formations.

shale-shells	495
sand-shale	560
red rock-shale	640
shale-shells	725
sand	945
red bed	1240
anhydrite	1275
shale-shells	1595
salt-shale	1700
shale-shells	1845
shale-lime-shells	2000
shale-lime	2335
lime-shale	2400
shale-lime	2745
lime-shale-	3050
lime	3161
lime-shale	3348 RTD
lime-shale	3363
Total Depth	

TOPS:

Topoka	2797-311
Heebner	3007-1321
Toronto	3032-134
Lansing-Kansas City	3052-1366
Base Kansas City	3267-1311
Arbuckle	3340-1347
RTD	3348-1342
Cable T.D.	3363

March 3, 1954- Murfin Drlg. Co.
trucks moved in tract unit.

March 4, 1954- 12 hrs. rigged
up and swabbed hole dry. Drilled
Cement.

March 5, 1954- Drilled Shoe,
Cleaned out to bottom. No free
oil. D.D. 3345 Few specks stained
Dolomite with little red shale. No
oil.

D.D. 3347- Very tight, pink dolomite,
no oil. Dumped one Bbl. acid. Let
stand overnight.

March 6, 1954- D.D. 3349- Let
stand overnight. Pink dolomite,
no oil.
Acid w/1000 gal with C-P Co. Fed
slow at 525# PSI.
Swabbed hole dry- no oil.

March 7, 1954- No oil after stand-
ing 12 hrs.
D.D. to 3363.

D& A