

10-8-17W^{pl}

TYPE



AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5422 EXPIRATION DATE

OPERATOR Abercrombie Drilling, Inc. API NO. 15-163-21,749

ADDRESS 801 Union Center WICHITA, KS 67202 COUNTY Rooks FIELD

** CONTACT PERSON Jack K. Wharton PHONE 316-262-1841 PROD. FORMATION

PURCHASER LEASE Head

ADDRESS State Geological Survey WICHITA BRANCH WELL NO. 1

DRILLING Abercrombie Drilling, Inc. 1980 Ft. from North Line and

CONTRACTOR ADDRESS 801 Union Center WICHITA, KS 67202 1980 Ft. from East Line of the NE (Qtr.) SEC 10 TWP 8S RGE 17W.

PLUGGING Abercrombie Drilling, Inc. WELL PLAT

CONTRACTOR ADDRESS 801 Union Center WICHITA, Kansas 67202

TOTAL DEPTH 3460' PBTD

SPUD DATE DATE COMPLETED

ELEV: GR 1919' DF 1922' KB 1924'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 244' DV Tool Used? NO

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

		x	
		10	

(Office Use Only)

KCC

KGS

SWD/REP

PLG.

A F F I D A V I T

Jack L. Partridge, being of lawful age, hereby certifies

that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Jack L. Partridge

SIDE TWO

OPERATOR Abercrombie Drilling LEASE HEAD

ACO-1 WELL HISTORY
SEC. 10 TWP. 8S RGE. 17W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Soil, Sand & Shale	0	246	<u>SAMPLE TOPS:</u>	
Sand & Shale	246	446		
Shale & Sand	446	1280	Anhydrite	1280' (+ 644)
Anhydrite	1280	1315	B/Anhydrite	1315' (+ 609)
Shale	1315	1450	Topeka	2841' (- 917)
Shale & Lime	1450	2130	Heebner	3055' (-1131)
Lime & Shale	2130	2546	Toronto	3078' (-1154)
Shale & Lime	2546	2922	Lansing	3098' (-1174)
Lime & Shale	2922	3030	Arbuckle	3416' (-1492)
Lime	3030	3460		
Rotary Total Depth	3460		<u>ELEC. LOG TOPS:</u>	
DST #1: (2992' - 3030') 30-45-		60-45. Fair Blow	Anhydrite	1282' (+ 642)
Rec. 370' MW - few spots oil.		IFPs: 99-129#,	B/Anhyd.	1315' (+ 609)
ISIP: 1057#, FFPs: 169-218#,		FSIP: 998#	Topeka	2842' (- 918)
DST #2: (3137' - 3208') 30-45-		60-45. Wk. Blow	Heebner	3654' (-1130)
Rec. 175' VSOSM. IFPs: 69-69#		ISIP: 1154#,	Toronto	3078' (-1154)
FFPs: 99-148#, FSIP: 1115#.			Lansing	3098' (-1174)
			B/KC	3334' (-1410)
			Arbuckle	3421' (-1492)
			LTD	3461' (-)

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	244'	Common	175	2% gel, 3% c.c.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD