

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- C-G DRILLING CO.
Farm- Bird No. 2

SEC.

15-163-01820
30 T. 8 R. 17W
SE NW NW

Total Depth. 3409
Comm. 11-22-53 Comp. 12-2-53
Shot or Treated.
Contractor.
Issued. 2-27-54

County Rocks
KANSAS



CASING:
8 5/8" 163.83'
5 1/2" 3+25'

Elevation. 1989' RB

Production. 240 BOPD

Meas. from top of R.B. Figures indicate Bottom of Formations
surface clay & sand 70
sand & shale 820
sand 1030
red bed 1300
anhydrite 1344
shale & shells 1975
lime & shale 3404
lime 3408 RTD
lime 3409
Total Depth

TOPS:
Anhydrite 1300
Topeka 2888
Hoebner 3101
Toronto 3121
Lansing 3142
Base KC 3367
Arbuckle 3401

DRILL STEM TESTS:

#1 3106-37' open 1 hr., w/
weak steady blow, rec.
490' gas & 150' fluid of
which 140' was HOCM & 10'
free oil w/1060# BHP.
#2 3235-42' open 1 hr., w/
mod. blow., rec. 40' muddy
oil, 80' oily SW & 195'
SW w/ 900# BHP & 100# FFP.
#3 3289-3303 open 1 hr. w/
fair steady blow, rec.
300' gas, 180' fluid of
which 85' was HO & GCM,
30' muddy oil & 65' clean
oil, w/1050# BHP & 25# FFP.

Drilled plug & DD to 3409 &
tested 1.25 BOPH. Acidized w/
750 gals. & swbd 20 BOPH.

Put on Pmp & State Pot. 1-14-54 of 240 BOPD.