

ROTARY DRILLING LOG

APR 10 1971

16-8-17W
SE SW NE
15-163-20359
Rotary Drilling Commenced 3/26/71

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Completed 4/4/71

LOCATION: Schindler "A" No. 1, SE SW NE Section 16-8S-17W,
Rooks County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Run 12 Jts. 8-5/8" Surface Casing set @ 241' KB. Cemented with
140 sacks. Completed 7:45 P.M. Circulated.

No oil string run. D & A. Plugged 2:00 P.M. April 4, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

95	Post Rock		
241	Shale & Shells	C.F.S.	
590	Shale	2850	3398
1292	Shale & Sand	3052	3407
1322	Anhydrite	3200	3410
1870	Shale	3243	3415
2065	Shale & Lime & Shale	3260	3420
2480	Shale & Lime	3276	3425
2635	Lime & Shale	3370	3430
2790	Shale & Lime	3382	3435
2970	Sandy Lime & Shale	3390	
3030	Shale & Lime		
3052	Lime		
3122	Lime & Shale	S.L.M.	
3220	Lime	Board 3074.19	
3243	Lime & Shale	Strap 3073.73	
3270	Shale		.46 Difference
3276	Lime		
3390	Lime & Shale		
3402	Lime		
3410	Arbuckle	Slope Tests	
3435	RTD	2000	
		2500	
		3000	

Log Left
anhydrite 1292
Hesbner 3065
Taranto 3088
Lansing 3108
Cher. Sd. 3353
Arbuckle 3403

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.