

15-103-30243

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **HOLLAR OIL & SHIELDS**

SEC. 18 T. 8 R. 17W
 LOC. NW NW NW

FARM **Maddy**

NO. 1

TOTAL DEPTH **3420**

COMM. **3-14-67**

COMP. **3-20-67**


SHOT OR TREATED

CONTRACTOR **Shields Drlg.**

ISSUED **4-22-67**

COUNTY **Rooks**

KANSAS



CASING

20	10	
15	8 5/8"	@ 184' w/135 SX
12	6	
13	5	

ELEVATION **1967'RB**

PRODUCTION **DRY/ARB**

FIGURES INDICATE BOTTOM OF FORMATIONS

..... Figures Indicate Bottom of Formations

Clay, post rock, shale & shells	100'
Shale	325'
Shale, sand & redbed	1,327'
Anhydrite	1,367'
Shale, shells & salt	1,750'
Shale & lime	2,180'
Lime	2,270'
Lime & shale	2,500'
Lime	2,655'
Lime & shale	2,885'
Lime	3,420'

100'
 325'
 1,327'
 1,367'
 1,750'
 2,180'
 2,270'
 2,500'
 2,655'
 2,885'
 3,420'

TOPS: SAMPLE

Topeka	2881
Heebner	3093
Douglas	3126
Lansing	3136
Base Kansas City	3361
Arbuckle	3397
Toronto	3117

R T D

NOTES

DST #1 3,120' - 73' Tool open 20 min. w/ weak blow for 6 min.
 Recovered 15' mud. IBHP-1,116#, IFP-55#,
 FFP-64#, FBHP-1,034#

DST #2 3,402' - 20' Tool open 30 min. w/ weak blow for 4 min.
 Recovered 10' mud. IBHP-467#, IFP-27#,
 FFP-37#, FBHP-64#