

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- MURFIN DRIG. CO.
 Farm- Stamper No. 1

SEC. 29 T. 8 R. 17W
 SE SE SE

15-163-00422

Total Depth. 3441
 Comm. 6-16-52 Comp. 6-27-52
 Shot or Treated.
 Contractor. Murfin Drig. Co.
 Issued. 8-30-52

County Rooks KANSAS



CASING:

8" 156'
 5" 3438'

Elevation. 1995 RB
 1993
 Production. 23 BOPD

Figures Indicate Bottom of Formations.

shale, sand, shells	100
shale, shells	156
cement	156
shale, shells	485
sand	540
shale, sand	855
sand	990
red bed, shells	1060
shale, shells, pyrite	1180
red bed, shale	1280
anhydrite	1318
red rock, shale, shells	1660
salt, shale	1750
shale, lime, shells	1945
shale, lime	2885
lime, shale	3155
lime	3441
lime	3450
Total Depth	

Tops:	
Anhydrite	1280
Topeka	2890
Heebner	3101
Toronto	3120
Lansing	3143
Reworked Arb.	3425
Arb. Dolo.	3436

Drilling in information:

Drilled to 3453 trace oil & 250' water after 5 hrs.

Set plug C 3366'

Perf. 3345 $\frac{1}{2}$ -51' 12 shots. Acidized w/1000 gals. test 15 gal. oil and trace wtr per hr.

Perf. 3304-10 12 shots oil inc. to 21 gal. per hr. Acidized 1000 gal. no inc.

Perf. 3230-32' test 3 bbl. wtr. $\frac{1}{2}$ bbl oil per hr.

Set plug @ 3222

Perf. 3208-14' 12 shots. Acidized 1000 gal. test 2 bbls. oil, 2 bbls. wtr per hr.