

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D.G. HANSEN
Farm- Bird

No. 6

SEC.

15-163-01824
30 T. 8
C N $\frac{1}{2}$ N $\frac{1}{2}$ NE

R. 17W

Total Depth. 3397'

Comm. 9-2-57

Comp. 9-10-57


Shot or Treated.

Contractor. C-G Drlg. Co.

Issued. 11-16-57

County Rooks

KANSAS



CASING:

8 5/8" 162'

5 1/2" 3377'

Elevation. 1957' DG

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface soil	162
sand-shale	510
sand	650
sdv shale	800
sand	1045
red bed	1295
anhdyrite	1335
shale-shells	1820
lime-shale	3385 RTD
lime-shale	3397
Total Depth	

TOPS:

Topeka	2856
Heebner	3067
Toronto	3094
Lansing/Kansas City	3109
B/Kansas City	3338
Basal Penn Lime	3355
Conglomerate	3373
Arbuckle	3378

DST #1--3100-3125. Open 1 hr.
Strong blow, Rec. 565' G above
395' F, 50' was GOCM & 345' CGD,
IBHP-1225#. FBHP-1105#. IFP-27#,
FFP-193#.

DST #2--3134-3156. Open 1/2 hr. Rec.
13' mud w/few specks of oil.

DST #3--3176-3198. Open 1 hr. Rec.
110' gas above 610' F, 60' was HO
& GCM, 545' MGO emulsion, 5' wtr.
IBHP-1257#, FBHP-1069#, IFP-100#,
FFP-265.

DST #4--3202-3209. Open 1 hr. Rec.
1560' G above 665' F, 485' was
CGO & 180' FSMGO. IBHP-1095#. FBHP-
1005#, IFP-0#. FFP-250#.

DST #5--3260-75. Open 1 hr. Rec.
650' g above 310' F, 10' was HOCM,
90' MO, 90' FO, & 120' CO. IBHP-1203#,
FBHP-1120#. IFP-0#. FFP-114#.

DST #6--3284-95. Open 1 hr. Rec. 25'
MOCM. IBHP-998#. FBHP-155#.