

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-01825

Company- D.G. HANSEN
Farm- Bird

No. 7

SEC. 30 T. 8 R. 17W
NE NE NE

Total Depth. 3354'

Comm. 9-12-57

Comp. 9-21-57


Shot or Treated.

Contractor. C-G Drilg. Co.

Issued. 11-16-57

County Rocks

KANSAS



CASING:

8 5/8" 172.87'

5 1/2" 3356.67'

Elevation. 1916' RH

Production. 25 BOPD

Figures indicate Bottom of Formations.

All Meas. from RB

surface soil	172
sand-shale	780
sand	950
sand-shale	1000
red bed	1260
anhydrite	1295
shell-shale	1440
shale-shells	1770
lime-shale	2100
lime	2300
lime-shale	3342 RTD
lime-shale	3354
Total Depth	

Tops;

Topeka	2819
Heebner	3032
Toronto	3058
Lansing/KC	3072
Base/Kansas City	3298
Basal Penn lime	3318
Arbuckle	3338

DST #1: 3062-86. Open 1 1/2 hrs.
Rec. 115' G / 65' F, 45' was
MOCM & 20' WOCM. IEHP-1195#.
BHP-233#. IFP-0#. FFP-57#.

DST #2: 3118-39. Open 1/2 hr. Rec.
30' VSOCM. IEHP-281#. FBHP-119#.

DST #3: 3134-58. Open 1 hr. Rec.
20' SOCM. IEHP-114#. FBHP-0#.

DST #4: 3157-70. Open 1 hr. Rec.
60' G above 445' F. 30' was
HOCM. 85' MO, 60' SMO, 270' CGO.
IEHP-1085#. FBHP-987#, IFP-0#.
FFP-176#.

DST #5: 3220-38. Open 1 hr. Rec.
235' G / 125' F, 40' was HOCM,
70' MO, 15' CO, IEHP-1215#, FBHP-1185#,
IFP-0#, FFP-68#.

DST #6: 3245-77. Open 1 1/2 hrs. Rec.
140' G above 100' MOCM. IEHP-1137#.
FBHP-745#.