

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- D.G. HANSEN
 Farm- Bird

No. 9

SEC. 30 T. 8 R. 17W
 NE NE NW

15-163-01827

County Rooks KANSAS



Total Depth. 3415'
 Comm. 4-3-58 Comp. 4-13-58
 Shot or Treated.
 Contractor. C-G Drlg. Co.
 Issued. 7-12-58

CASING:
 8 5/8" 160'
 5 1/2" 3399'

Elevation. 1985' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

All Meas. fr top RB
 shale, sand 850
 sand 1025
 red bed 1300
 anhydrite 1337
 shale, shell 2180
 lime, shale 3085
 lime 3143
 lime, shale 3157
 lime 3309
 lime, shale 3363
 lime 3402 RTD
 lime 3415
 Total Depth

TOPS:
 Heebner 3096
 Toronto 3115
 Lansing 3136
 B/Kansas City 3363
 Arbuckle 3398

DST #1- 3102-25. Open 1 1/2 hrs
 Strong blow. Rec. 850' G, 565'
 fluid of which 60' OCM, 60' MO,
 445' CO. IB P-1180#. FBHP-1105#.
 IFP-20#. FFP-205#.

DST #2 - 3128-57. 1 1/2 hr. Rec.
 18' HOCM. IBHP-10#. FBHP-30#.

DST #3 - 3204-30. 1 1/2 hr. Rec.
 40' G, 25' MOCM. IBHP-75#.
 FBHP-75#.

DST #4 - 3229-401 Op. 1 hr. Rec.
 900' & 1150' F of which 1000' was
 O & 150' SMO. IBHP-1060#, FBHP-1005#.
 IFP-190#. FFP-430#.

DST #5 - 3321-45. 1 1/2 hr. Rec. 230' F
 which was 40' O & GCM, 60' HOCM, 30'
 MO & 100' O. IBHP-740#. FBHP-710#.
 IFP-40#. FFP-75#.