


15-163-0B19

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHELL OIL
Farm- H. A. Krug No. 8

SEC. 19 T. 8 R. 17W
NW SW SW

Total Depth. 3416'
Comm. 11-28-53 Comp. 1-9-54
Shot or Treated.
Contractor.
Issued. 3-6-54

County Rooks
KANSAS


CASING:
8 5/8" 1319'
5 1/2" 3409'

Elevation. 1993
Production. 339 Bbls. & NW

Figures indicate Bottom of Formations.

shale	45
sand	50
shale & shells	520
sand	550
sand	650
shale & shells	810
shale	915
sand & shale	1030
red bed	1309
anhydrite	1352
shale & shells	1700
shale	1800
lime & shale	2775
shale & shells	2800
lime	2835
shale	2838
lime	2865
sand	3872
lime	2896
lime	2938
shale red & black	2946
lime	2995
shale dark grey	2997
lime	3005
shale red & grey	3008
lime	3033
shale red & grey	3038
lime	3056
shale	3058
lime	3109
shale black	3110
lime	3131
lime	3149
lime	3323
shale red & grey	3327
lime	3334
shale red & grey	3336
lime	3408
3408 equals 3410 S.L.C.	
dolomite	3416
Total Depth	

Tops:

Topeka	2896
Heebner	3109
Toronto	3131
Lansing-Kans. City	3149
Arbuckle	3408

1,000 acid 3409-3416