

15-163-0362


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. D. G. HANSEN
Farm- Reeder No. 1

SEC. 19 T. 8 R.17W
NE SW SE

Total Depth. 3388
Cased 4-10-57 Comp. 4-19-57
Blind or Treated.
Contractor. C-G Drilling Co.
Date 7-13-57

County Rooks
KANSAS



8 5/8 @ 162.36'
5 1/2 @ 3373'

Elevation. 1957 RB
Production. 25 BOPD

Figures indicate Bottom of Formations.

surface soil	162
shale & sand	810
sand	1020
red bed	1278
anhydrite	1310
lime & shale RTD	3380
lime & shale	3388
Total Depth (RBM)	

TOPS: (RBM)	
Anhydrite	1278
Topeka	2855
Heebner	3065
Toronto	3086
Lansing-KC	3106
Base KC	3336
Basal Penn. Lime	3352
Arbuckle	3371

DST #1: 3071-3100, open 1 hr. wk. bl. thruout, rec. 33' med. OCM, IBHP 925#, FBHP 137#

DST #2: 3181-3200, open 1 hr. intmnt. wk. bl. rec. 9' HOC gassy mud, 30' SOC gassy mud, IBHP 1157#, FBHP 118#

DST #3: 3203-15, open 1 hr. fair bl. thruout, rec. 42' HOCM, 30' wtry OCM est. @ 40-50% wtr. IBHP 1205#, FBHP 912#, FFP 75#.