

15-163-70056

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- CITIES SERVICE OIL CO.
 Farm- Reoder No. 2

SEC. 19 T. 8 R. 17W
 CW $\frac{1}{2}$ W $\frac{1}{2}$ SE
 1320' fr S & 330' E of Center

Total Depth. 3379'
 Comm. 12-10-53 Comp. 12-28-53
 Shot or Treated. 1000 gals. 12-29-53
 Contractor. Lohmann-Johnson Drlg. Co., Inc.
 Issued. 3-13-54

County Rooks

KANSAS



Elevation. 1951 DF

Production. I.P. 120 oil & no
 wtr in 24 hrs.

Figures indicate Bottom of Formations.

lime & shale	157
shale	240
shale & shells	1061
red bed	1268
anhydrite	1305
lime & shale	1310
shale & shells	1895
broken lime	2010
shale & lime	2155
lime & shale	2575
shale	2720
shale & lime	2870
lime & shale	3206
lime	3285
lime & shale	3335
lime	3374
3374 RTD - 3372 SLM	
lime	3379
Total Depth	

Tops:
 Corr. Topeka 2854
 Corr. Hoebner 3063
 Corr. Dodge 3083
 Corr. Lansing 3102
 Corr. Arbuckle 3371
 Penetration 8

bailed 34 gals. oil/hr./10 hrs.
 2-stage cementing collar at 1286' with
 300 sacks cement and 75 sacks Stratacrete.

Slope Tests (Acid Bottle):

500' 0°
 1000' 0°
 1500' 0°
 2000' 0°
 2500' 0°
 3000' 0°

7-7/8" rotary hole