

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-D1364

Company- D. G. HANSEN
Farm- Reeder No. 3

SEC. 19 T. 8 R. 17W
CS/2 S/2 SE

Total Depth. 3394'
Comm. 8-13-57 Comp. 8-22-57
Shot or Treated.
Contractor. C-G Drilling Co.
Issued. 10-19-57

County Rooks
KANSAS



C/SING:
8 5/8" 166'
5 1/2" 3409'

Elevation. 1961 DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

All measurements taken from top of rotary bushing.

surfact soil	166	
shale	825	
sand	1050	
red bed	1286	
anhydrite	1325	
shale-lime	1560	
shale-shells	1920	
shale-lime	2080	
lime-shale	3286	
lime	3331	
lime-shale	3390	RTD
Lime-shale	3394	CTD
Total Depth		

TOPS:
Anhydrite (scout) 1286
Topeka 2870
Heebner 3077
Toronto 3097
Lansing Kans. City 3118
Base Kansas City 3348
BP Lime 3366
Arbuckle 3386

D.S.T. #1 3083-3112, open 1 hr. Rec.
485' gas above 295' fluid, 35' MOCM, 60'
HOCM, 200' of MGCO. IBHP-1110#.
FBHP-645#. IFP-50#. FFP-130#.

D.S.T. #2 3108-3135. Open 1 1/2 hrs. Rec.
180' gas plus 75' HOCM. IBHP 1222#.
FBHP-310#.

D.S.T. #3 3185-3210. Open 30 Min. Rec.
7' mud. FBHP--105#.

D.S.T. #4 3209-3219. Open 1 hr. Rec.
360' MW. IBHP-1153#. FBHP-825#. IFP-30#.
FFP-185#.

D.S.T. #5 3268-3286. Open 30 Min. Rec.
12 mud, few spots of oil. IBHP-1067#.
FBHP-865#.

D.S.T. #6 3306-3331. Open 1 hr. Rec.
23' MOCM. IBHP-829#. FBHP-140#