

15-163-03950


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.  
Farm- Reeder No. 3

SEC. 19 T. 8 R. 17W  
C S/2 N/2 SE  
1650' N & 1320' W of SE  
Corner.

Total Depth. 3363'  
Comm. 5-26-58 Comp. 6-17-58  
Shot or Treated.  
Contractor. Lohmann-Johnson Drilg. Co.  
Issued. 9-13-58

County Rooks KANSAS



Elevation. 1919' Gr.

CASING:  
8 5/8" 240' cem w/175 sx.  
5 1/2" 3342' cem w/175 sx.  
DV tool 1274' w/300 sx & 150 cu. ft. Stratacrete.  
Figures Indicate Bottom of Formations.

Production. 51 BO & 4 BWPD

shale	540
shale & lime	1255
anhydrite	1286
shale & lime	1800
lime	2590
lime & shale	2720
lime	3346
3346 RTD = 3342 SLM	
lime	3363
Total Depth	

TOPS: CORR:

Topeka	2852
Heebner	3035
Dodge	3057
Lansing	3075
Base Kansas City	3302
Arbuckle	3341
Pen.	22

22' oil in 1 hr at 3355  
97' oil in 12 hrs at 3355.  
6-13-58 Acidized 2000 gals. 3342-55.  
6-18-58 Set packer at 3359; acidized  
1000 gals. 3359-63.