

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-163-01365

Company- D. G. HANSEN  
Farm- Reeder No. 4

SEC. 19 T. 8 R.17W  
SE SE SE

Total Depth. 3379'  
Comm. 10-10-57 Comp. 10-18-57  
Shot or Treated.  
Contractor. C-G Drilling Co.  
Issued. 12-28-57

County Rooks KANSAS



CASING:

8 5/8" 169.95'  
5 1/2" 3359'

Elevation. 1934' DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

All measurements taken from top of Rotary Bushing

sand-shale	795
sand	1025
red bed	1275
anhydrite	1315
sand-shale	1650
lime-shale	3362 RTD
lime-shale	3379 CTTD
Total Depth	

TOPS:		
Anhydrite	(Scout)	1275
Topeka		2840
Heebner		3052
Toronto		3071
Lansing/KC		3092
Base/KC		3320
Basal Penn. Lime		3338
Arbuckle		3357

D.S.T. #1. 3057-85. Open 1/2 hr. Rec.  
10' M with few specks oil. BHP 56#.  
D.S.T. #2. 3083-3108. Open 1 1/2 hrs.  
Rec. 25' G & 40' MOCM. IBHP 1113#.  
FBHP 116#.  
D.S.T. #3. 3136-55. Open 1 1/2 Hrs. Rec.  
110' gas above 70' MOCM. IBHP 1203#.  
FBHP 255#.  
D.S.T. #4. 3173-92. Open 1 hr. Rec.  
445' G above 220' F, 50' was MOCM, 20'  
HOCGM, 75' MGO, 60' SMGO, 15' W. IBHP  
1100#. FBHP 912#. FFP 115#.  
D.S.T. #5. 3237-3260. Open 1 hr.  
Rec. 600' G above 430' F, 65' was HOCM,  
115' MO, 60' SLMO & 190' CO. IBHP  
1220#. FBHP 1128#. FFP 210#.  
D.S.T. #6. 3266-3300. Open 1 1/2 Hrs.  
Rec. 60' G above 95' F, 30' HOCM &  
65' MOCM. IBHP 1200#. FBHP 185#.  
FFP 24#.