

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


API No. 15 - 163 - 21,132
County Number

State Geological Survey
WICHITA, BRANCH

S. 19 T. 8S R. 17W
Loc. C NE 1/4 NE 1/4 NE 1/4

County Rooks

640 Acres
N



Locate well correctly

Elev.: Gr. 1892

DF 1894 KB 1897

Operator
The Gene Brown Company

Address
407 S. Main

Well No. 1 Lease Name Stamper

Footage Location
330 feet from (N) (S) line 2316 330 feet from (E) (W) line 990

Principal Contractor *Lawrence D. Dyer* Geologist *Eric Woodell*

Spud Date 8/26-80 Date Completed 9/4-80 Total Depth 3380 P.B.T.D. 3369

Directional Deviation Oil and/or Gas Purchaser *Petco Service*

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	156	Common	65	
Long String	7-7/8"	4 1/2"	9 1/2#	3379	60/40 Pcp	150	8% Salt 4% gel 1 Sack gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	3/8"	3330 - 3356

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2500 Gal 28% Acid	3330 - 3356

INITIAL PRODUCTION

Date of first production *Nov 20 - 1980* Producing method (flowing, pumping, gas lift, etc.) *Pumping*

RATE OF PRODUCTION PER 24 HOURS
Oil 25 bbls. Gas MCF 50 bbls. Water Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) *Vented* Producing interval (s) *Subsable 3330-3356*

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans- mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator *The Lee Brown Co.*

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: *Oil*

Well No. *1*

Lease Name *Stamps*

S. *19* T. *8* R. *12* W.

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			<i>Jopoka</i>	<i>2817 - 920</i>
			<i>Neabner</i>	<i>3027 - 1130</i>
			<i>Toronto</i>	<i>3049 - 1152</i>
			<i>L.H.C.</i>	<i>3069 - 1172</i>
			<i>Base H.C.</i>	<i>3296 - 1399</i>
			<i>Mumator SD</i>	<i>3301 - 1404</i>
			<i>Simpson</i>	<i>3324 - 1427</i>
			<i>Bel</i>	<i>3329 - 1432</i>

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Thomas E. Brown
Signature

Owner
Title

1/20 - 1981
Date