


15-103-01371

PHILLIPS PETROLEUM CO. & CONTINENTAL OIL CO.  
Henruss No. 1

SEC. 31 T. 8 R. 17 W.  
CNE NW  
660' NL 754' EL NW  $\frac{1}{4}$

Total Depth. 3402  
Comm. 3-22-42 Comp. 4-29-42  
Shot or Treated.  
Contractor.  
Issued. 6-6-42

County Rocks



CASING.

8" 1307  $\frac{1}{2}$ '  
5  $\frac{1}{2}$ " 3398'

Elevation.

Production. Pot. 402 B.  
No wtr.

Figures Indicate Bottom of Formations

surface sand and shale	80
shale and shells	820
sand	860
lime and shale	1045
pyrites and shale	1095
red bed	1296
anhydrite	1308
anhydrite	1340
red bed	1430
shale and lime shells	1612
red bed and shale	1660
salt and shale	1720
shale lime and shells	2050
shale shells and lime	2295
shale and shells	2360
lime	2377
shale and lime shells	2459
shale and shells	2524
shale breaks in lime	2595
shale and lime shells	2737
shale lime and shells	2939
lime and shale	3010
lime	3067
shale and lime	3239
shale lime and chert	3299
cored - dense lime	3305 $\frac{1}{2}$ '
lime	3400
lime	3402

Total Depth.

Pot. 402 bbls, no wtr after 2500 gal

Top Anhydrite	1300'
Topeka	2886
Lansing Kansas City	3126
Arbuckle	3398