

13-8-18W

State Geological Survey
WICHITA BRANCH

W E L L L O G

OPERATOR: Geodessa Corporation

WELL NAME: Lonnecker "A" #1 LOCATION: SW SE SE 13-8s-18W

COUNTY: Rooks STATE: Kansas

WELL COMMENCED: September 23, 1981 WELL COMPLETED: September 30, 1981

ELEVATION: 1964' K.B. TOTAL DEPTH: 3447'

PRODUCTION: Oil RIG NO: #1

CASING - 8 5/8": 6 Jts new 20# tallied @ 252.51' set @ 259' cemented with 140 sxs common 3% cc 2% gel P.D.@ 6:00 P.M. 9-23-81 did circ.
 5 1/2": 82 Jts new 14# tallied @ 3448.90' set @ 3446' cemented with 10 BBL salt flush 150 sxs common 10% salt 5# gilsonite 3/4 of 1% CFR 2 P.D.@ 9:30 P.M. 9-30-81

MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	200'	sand and shale		
200'	260'	sand and shale	260' - 1 degree	
260'	311'	sand and shales		
311'	1322'	sand and shales		
1322'	1362'	anhydrite		
1362'	1441'	shales		
1441'	2002'	sand, shales, and lime		
2002'	2035'	shale and lime	2035' - 1 1/2 degree	
2035'	2157'	shales and limes		
2157'	2442'	shales and limes		
2442'	2719'	lime and shale		
2719'	2942'	limes and shales		
2942'	3080'	limes and shales		
3080'	3213'	lime and shale		
3213'	3316'	lime and shale		
3316'	3382'	lime and shale	3382' - 1/4 degree	
3382'	3415'	lime and shale		
3415'	3429'	lime and shale		
3429'	3447'	lime and shale		
3447'	R.T.D.			

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1981

CONSERVATION DIVISION
Wichita, Kansas