

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

15-1103-00386

COMPANY WESTGATE-GREENLAND OIL CO.

SEC. 17 T. 8 R. 18W

FARM Bunberry

NO. 1

LOC. SE SW NW

TOTAL DEPTH 3436

COMM. 6-17-50

COMP. 6-28-50


SHOT OR TREATED

CONTRACTOR Jackson Drilling Co.

ISSUED 11-18-50

COUNTY Rooks

KANSAS



CASING

5/8" 200' cem. w/135 sx.
5 1/2" 3404' cem. w/75 sx.

ELEVATION 1980

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

shale & shells	90
shale	360
shale & shells	445
shale	570
sand w/shale	860
sand	1085
red bed	1205
shale, red bed & sand	1307
anhyd.	1418
shale & shells	1795
shale w/lime	1840
shale & lime w/salt	1900
lime sdy	1960
lime & shale	2180
shale, shells	2380
lime, shale	3108
shale	3153
lime	3371
shale & lime	3385
congl.	3402
Arb. R.T.D.	3411
Arb.	3436
Total Depth	

Tops:	
Anhyd.	1370
Heebner	3104
Lansing	3147
Arbuckle	3400

ALL MEASUREMENTS FROM TOP OF DERRICK FLOOR

D.S.T. 3400-3409, open 1 hr. rec. 70' heavy oil cut mud, show oil at 3411.
5000 GA Dowell Service, 1000 GA add. 500 GA add., swabbed 1 1/2 bbls. oil per hr. Drilled to 3436, 500 GA add. Halliburton squeezed off Arb. 3436-3430. cem. w/50 sx.
1000 GA Dowell Service, swb. 2 1/2 BOPH.