

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- CITIES SERVICE OIL CO.
Farm- Kriley No. 1

15-163-70746
SEC. 24 T. 8 R. 18W
SE SE SW
330' N & 330' W of S/4C

Total Depth. 3417
Comm. 10-3-53 Comp. 10-21-53
Shot or Treated. Acid 1000 gals.
Contractor. Braden Drilling Co.
Issued. 12-19-53

County Rooks

KANSAS



Elevation. 2000

Production. 123 BO, 5 BW

Figures indicate Bottom of Formations.

CASING:

8 5/8 @ 240' w/ 175 sx cmt.
5 1/2 @ 3411' w/ 175 sx cmt.

lime	50
chalk	90
sand	130
shale & shells	410
sand, shale & shells	1245
red bed	1325
anhydrite	1365
shale & shells	1975
broken lime	2160
lime	2200
broken lime & shale	2655
shale	2940
broken lime	3015
lime & shale	3065
broken lime	3120
lime	3271
lime & shale	3332
lime (SLM 3413)	3417
lime	3417
Total Depth	
TOPS: (corr.)	
Topeka	2900
Heebner	3109
Dodge	3127
Lansing	3150
Arbuckle	3410
Penetration	7

11 gasl. oil per hr.