

oil

Abercrombie Drilling, Inc.
Abercrombie Drilling, Inc.
THOMAS #1
SW NE NE, Sec. 24-8S-18W
Rooks County, Kansas
Jack K. Wharton
December 5, 1969
December 12, 1969

0	115	Rock
115	500	Shale
500	765	Sand
765	865	Shale
865	1025	Sand
1025	1030	Shale
1030	1313	Shale (Red Bed)
1313	1347	Anhydrite
1347	1935	Shale
1935	2240	Lime & Shale
2240	2500	Shale & Lime
2500	2952	Lime & Shale
2952	3413	Lime
	3413	Rotary Total Depth

ELEVATION:

Anhydrite	1314	(+ 666)	1981'	K.B.
Heebner	3105	(-1125)	1979'	D.F.
Toronto	3126	(-1146)	1973'	G.L.
Lansing	3146	(-1166)		
Arbuckle	3407	(-1427)		
E. Log T.D.	3413	(-1433)		

Drilled 250' of 12-1/4" surface hole and set 8-5/8" surface casing @ 242' w/160 sx. Sunset cement. Cement circulated. Plug was down at 1:00 A.M., 12-5-69. Set 4-1/2", 9-1/2" csg. @ 3409. Cemented w/35 sx. 5Q-50 posmix w/2% gel, 12# gilsonite per sx., and 65 sx. common cement w/2% gel, 10% salt, 1% c.c. and 2# friction reducer. Set plug @ 10:30 P.M., 12-12-69.

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Thomas #1, SW NE NE, Section 24-8S-18W, Rooks County, Kansas.

Jerzy A. Langrehr