

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-03413

Company. D. G. HANSEN
Farm. McMillen

No. 1

SEC. 25 T. 8 R. 18W
SW SE NE

Total Depth. 3418

Comm. 8-1-55

Comp. 8-9-55


Shot or Treated.

Contractor. C-G Drilling Co.

Issued. 10-22-55

County Rooks

KANSAS



Elevation. 1994 DF

Production. 25 BOPD

8 5/8 CASING:
5 1/2 165'
3423.52'

Figures indicate Bottom of Formations.

sand & shale	165
shale	520
sand	630
shale	765
sand & shells	1030
sand & red bed	1312
anhydrite	1347
shale	1400
shale & shells	1840
lime & shale	3413
lime	3418
Total Depth	

RTD

TOPS:

Anhydrite	1310
Topeka	2897
Heebner	3109
Toronto	3129
Lansing	3149
Base K. C.	3376
Arbuckle	3410

All RB Meas.

DST #1: 3152-60, open 1 hr, wk. bl.
incr. to strong, rec. 820' gas, 230'
clean oil, BHP 1030#

DST #2: 3303-11, open 1 hr. very wk.
bl. 8 min. rec. 33' fluid, (32' wtr.
& 1' oil) BHP 900#

DST #3: 3316-22, light bl. incr. to
steady, rec. 60' HO&GCM, BHP 1175#