

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00959

Company- CARL TODD DRILLING COMPANY
Farm- Welch No. 1

SEC. 32 T. 8 R. 18W
SW SE NE

Total Depth. 3520
Comm. 11-5-56 Comp. 11-14-56
Shot or Treated.
Contractor.
Issued. 12-15-56

County Rooks KANSAS



8 5/8" CASING:
200' cem w/150 sx.

Elevation. 2047

Production. Dry

Figures Indicate Bottom of Formations.

shale	125
shale, shells	200
shale	580
shale, sand	780
sand	840
shale, shells	940
sand shale	1200
red bed, shale, shells	1405
shale, shells	1450
anhydrite	1490
shale, shells	1690
shale, shells, salt	1900
lime, shale	2285
lime broken	2395
lime, shale	2565
lime	2645
lime, shale	2940
lime	3005
lime, shale	3090
lime,	3345
lime, chert	3380
lime	3438
congl.	3489
Arbuckle RTD	3520
Total Depth	

Tops:
Anhydrite (Scout) 1450
Topeka 2977
Heebner 3191
Toronto 3211
Lansing 3231
Arbuckle 3489

DST #1 3198-3278, open 1
hr., rec. 26' mud slightly
oil specked, BHP 960#.

DST #2 3278-3315, open 30
mins., rec. 10' mud, BHP 0#.

DST #3 3482-95,
tec. 7' mud, BHP