


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - HUPER & PRIME DRILLING CO.
Farm - Bieker No. 1

15-163-00242
SEC. 33 T. 8 R. 18W
SW SW SE

Total Depth. 3540
Comm. 8-4-49 Comp. 8-17-49
Shot or Treated.
Contractor. Prime Drilling
Issued. 10-8-49

County. Rocks
KANSAS



Elevation. 1987' 2nd

Production. Dry

Figures indicate Bottom of Formations.

surface clay	60
sand	100
shale	180
shale, shells	195
shale	360
shale, shells	855
sand	1080
shale shells	1360
anhydrite	1395
shale, shells	1440
red bed, shale	1480
shale shells	1700
salt, shells	1765
lime, shale	1900
lime, shale, shells	1975
lime, shale	2884
sand	2891
lime shale	3045
lime	3150
lime, shale	3180
lime	3415
lime, shale	3490
chert	3525
lime cherty	3540
Total depth	

Sample Tops:	
Severy sand	2884
Topeka	2918
Heebner	3145
Toronto	3166
Lansing	3184
Arbuckle	3517

DST 2883-91, open 55 mins, rec.
320' blakish water.
DST 3157-80, open 30 mins, blow 5
mins, rec. 8' mud.
show oil. 3220-25.
DST 3213-36, open 1 hr, rec. 66' salt water
and mud, very slightly gas cut. BHP 950#.
Show oil. 3265-72.
DST 3255-75, open 30 mins, rec. 6' of
very slightly gas cut mud.
Rm Schlumberger.